



WALMAN INFRA & ENERGY PVT. LTD.
+PMC+DESIGN+CONSTRUCTION

ANNEXURE 2

Section 6, Amendments to EMPLOYER'S REQUIREMENT

Except following changes , All clauses / clause number remain same of the Eligibility Criteria given in the Tender Document

For any discrepancy of any kind, Original Tender document of respective part will be considered

Cl. 1.18 shall be read as under:

1.18 BORROW AREAS AND DISPOSAL OF MATERIALS

a) Excavated surplus materials:

The contractor shall dispose-off all excavated surplus materials and spoils to muck disposal areas designated by the Employer and indicated in the bid document. Usable excavated materials shall be stacked separately for subsequent extraction and use.

b) Borrow Areas and Stockpiles

The Contractor shall submit management plan for extracting, processing and stockpiling stone/ sand material from designated quarry/ borrow area indicated in the bid document for the Employer's approval.

It shall be the responsibility of the Contractor to ascertain the suitability of the materials as per technical specifications mentioned in the contract and obtain prior approval of the Employer. The Contractor shall pay all necessary costs towards fees, taxes, levies or royalties to the appropriate parties/agencies/authorities and follow all relevant regulations. The Contractor shall keep the borrow pits free from ponding water and shall carry out necessary erosion protection and other mitigation measures as acceptable to the Employer.

Where suitable material is stockpiled for later use, the Contractor shall ensure that the formation is cleared of all vegetation unless otherwise approved by the Employer. Stockpiled material shall be finished with a sloping surface to ensure run-off to keep the stockpile free of ponding water. Wherever required the Contractor shall provide a drainage ditch around the stockpile to prevent the ingress of water or other measures acceptable to the Employer.

The Contractor shall also be responsible for disposal of surplus materials to designated places as approved by Employer. The muck disposal area shall be duly prepared and protected to prevent spillage of muck beyond designated area. Mucks shall be compacted progressively by the passage of muck hauling vehicle and construction equipment. The slope of muck dump shall be protected against erosion. On completion of work all muck disposal area shall be restored by laying top soil layers and growing vegetation.

Sufficient time shall be allowed for notification as may be required by the relevant authorities so that appropriate action can be taken regarding the execution of the removals and relocation.



WALMAN INFRA & ENERGY PVT. LTD.
+PMC+DESIGN+CONSTRUCTION

In the event that the borrow areas, quarries, and/or dumping yards identified as per the bid documents are insufficient to meet the actual requirements of the Project, the Contractor shall identify and propose additional borrow areas, quarries, and/or dumping yards much in advance for the prior written approval of the Employer.